


REVISION 0	REFERENCE EEAM-Q-009		
DOCUMENT TYPE SPECIFICATION		AUTHORISATION DATE: Date signed by CEO	
TITLE: QUALITY MANAGEMENT SPECIFICATION FOR SUPPLIER/CONSTRUCTION		PAGE 1 of 14	
COMPILED BY:	REVIEWED BY:	REVIEWED BY:	
SENIOR MANAGER (QUALITYMANAGER)	SENIOR MANAGER (PROJECT MANAGER)	SENIOR MANAGER (GENERAL MANAGER)	
ACCEPTED BY:		AUTHORIZED BY:	
CHIEF FINANCIAL OFFICER		CEO	
FUTURE REVISION RECORD NUMBER	DESCRIPTION OF REVISION	APPROVAL	DATE 01/03/2010
-1-			
CONTENTS			
1.0 QUALITY MANAGEMENT SPECIFICATION FOR SUPPLIER/CONSTRUCTION			

KEYWORDS SPECIFICATION	DATE OF LAST REVIEW: N/A
	DATE OF NEXT REVIEW: 01/03 2010

DETAILS CONTENTS

Title		Page
-------	--	------

Table of Contents

1.	Introduction	1
2.	Definitions	1
3.	Applicable Documents	2
3.1	General.....	2
3.2	Statutory Regulations	2
3.3	Codes and Standards.....	2
4.	Quality System	3
4.1	General.....	3
4.2	Supplier/Contractor Quality System Requirements	3
4.3	Supplier/Contractor Documentation Requirements.....	3
5.	Quality Assurance	3
5.1	Project Quality Plan	3
5.2	Procedures	4
5.2.1	Document Control	4
5.2.2	Design Control	5
5.2.3	Procurement.....	5
5.3	Supplier/Contractor Audits.....	5
5.4	Transnet Port Terminals Audit.....	5
6.	Inspection and Testing	5
6.1	General.....	5
6.2	Quality Control Plans	6
6.3	Inspection Points	6
6.4	Revision to Quality Control Plans	6
6.5	Kick Off Meeting	7
6.6	Schedule of Inspection	7
6.7	Field Inspection Checklists.....	7
6.8	Inspection Notification	7
6.9	Inspection and Testing	7
6.10	Inspection Release.....	8
6.11	Special Processes.....	8
6.12	Welding Procedures.....	8
6.13	Material Traceability	9
6.14	Material Certification	9
7.	Non Conforming Products	10
7.1	General.....	10
7.2	Corrective and Preventative Action	10
8.	Concession Requests and Technical Queries	10
8.1	Concession Requests	10
8.2	Technical Queries	10
9.	Inspection, Measuring and Test Equipment	11
9.1	Calibration	11
9.2	Use of Inspection, Measuring and Test Equipment	11
9.3	Verification of Previous Test Results.....	11
10.	Quality Records	12
	Annexure A - Sample Quality Control Plan	13
	Annexure B – Request for Concession	13

1. Introduction

This Specification outlines the minimum requirements to ensure that products and services supplied to Transnet Port Terminals are manufactured, provided, constructed or installed in accordance with all specified requirements as defined in the Contract, all associated specifications, drawings, codes and standards.

2. Definitions

Term, Abbreviation	Meaning
Data	All drawings/documents/data/information and DP's required to be supplied under the Contract
Data Pack (DP)	A compilation of manufacturing data, certification, inspection and testing records prepared by the Supplier/Contractor to verify compliance with the Contractual requirements.
Employer	For the purposes of this document, the term Employer has the same meaning as applied to the term Client.
Field Inspection Checklist (FIC)	A document that details the checks, requirements and test parameters for each type of equipment to permit field installation and pre- commissioning of the equipment.
TPT	Transnet Port Terminals is the Employer's Nominated Agent in terms of the Conditions of Contract.
Inspection Release Report (IRR)	A document issued to the Supplier/Contractor by TPT advising release of the Materials for shipment. This does not relieve the Supplier/Contractor of its obligations in accordance with the Terms and Conditions of the Contract.
Inspection Waiver Report (IWR)	<p>A document issued to the Supplier/Contractor by TPT advising that TPT has waived final inspection for the materials listed in this document. The issue of this Report does not preclude further inspection by TPT, is issued without prejudice and does not relieve the Supplier/ Contractor from the guarantees and obligations included in the Contract/ Contract.</p> <p>A document prepared by the Supplier/Contractor providing relevant information applicable to the installation and maintenance of the specific equipment, including consumables (eg. oils etc)</p>
Project Quality Plan (PQP)	A document that outlines the Supplier/Contractor's strategy, methodology, resources allocation, Quality Assurance and Quality Control coordination activities to ensure that Goods and Services supplied meet or exceed the requirements defined in the Contract, drawings, codes and standards.
Quality Control Plan (QCP)*	<p>A document outlining specific manufacturing / construction inspection and testing requirements, including responsibilities, test acceptance criteria, nomination of witness and hold points.</p> <p>For the purposes of this document, the term Supplier/Contractor has the same meaning as applied to the term Sub-Supplier/Sub-Contractor</p>
Supplier/Contractor	This refers to the documentation required to be submitted by the relevant Supplier / Contractor in terms of the Contract.
Supplier/Contractor Data Requirements	These requirements are generally tailored to suit the particular Scope of Work, although it also addresses the manner in which the documentation is required to be submitted, eg Hard copy, Electronic copy etc
Technical Query Note (TQN)	This refers to a document used by the Supplier/Contractor to formally clarify a Technical Query related to the scope of supply. This should not be used where a non-conformance has already been initiated.

3. Applicable Documents

3.1 General

All work performed shall comply with the requirements of this Specification, the documentation referenced in the Contract and the latest revision/edition of the relevant Codes and Standards referenced herein.

3.2 Statutory Regulations

Occupational Health & Safety Act, Act No 85, of 1993 and Regulations as amended.

3.3 Codes and Standards

Document No.	Title
ISO 9001	International Standard Series Quality Systems
EEAM-Q-013	Punch Listing Standard

4. Quality System

4.1 General

The Supplier/Contractor shall be responsible for all quality activities necessary to ensure the Work meets the requirements specified in the Contract, and shall manage and coordinate all Quality aspects of Work in accordance with the requirements of this Specification, and the Supplier/Contractor's PQP and QCP's once reviewed and approved by TPT.

The Supplier/Contractor shall ensure that all Sub-Suppliers/Sub-Contractors also conform with the requirements of this Specification.

4.2 Supplier/Contractor Quality System Requirements

The Supplier/Contractor shall have, maintain and demonstrate its use to TPT, its documented Quality Management System. The Supplier/Contractors Quality Management System should be in accordance with the International Standard ISO 9001.

The Supplier/Contractor shall submit its Quality System documentation to TPT at the time of tender and at Contract Phases as detailed below:

- Project Quality Plan
- Quality Policy
- Index of Procedures to be used
- Programme of internal and external audits

4.3 Supplier/Contractor Documentation Requirements

The Supplier/Contractor shall develop and maintain a comprehensive register of documents that will be generated throughout the project, and shall include all quality related documents. The register shall be submitted to TPT for review.

TPT shall indicate those documents required to be submitted for information/review and/or acceptance and this shall be indicated in the Supplier/Contractors' Document Register. The register shall indicate the dates of issue of the documents taking into account sufficient time to allow TPT review/acceptance cycle prior to the document being required for use.

5. Quality Assurance

5.1 Project Quality Plan

Where specified, the Supplier/Contractor shall submit a PQP to TPT within 28 days after the Contract start date. The PQP shall detail how the Supplier/Contractor's Quality System will be applied to the Scope of Work specified in the Contract, and shall address the following:

- Satisfying the technical and quality requirements of the Supplier/Contractor's Scope of Work, and relevant elements of the applicable ISO 9001 standard
- include all quality activities relevant to the Scope of Work, identifying all procedures, reviews, audits, controls and records used to control and verify compliance with the specified Contractual requirements

Include a listing of all special processes (eg. welding and non-destructive testing, cube testing etc) envisaged for use, including confirmation of personnel certification as required

- Include all proposed method statements (for site based work activities)
- Include a description of the Supplier/Contractor's project organisation, with key positions and responsibilities identified and individuals named. The organisation structure shall also indicate the resources committed to the management / coordination of QA / QC activities
- Include a listing of all Quality Control Plans (QCP's), and associated Field Inspection Checklists (FIC's), as applicable
- Identify in the Project Quality Plan any Sub-Supplier/Sub-Contractor work. Sub-Supplier/Sub-Contractor plans shall be approved by the Supplier/Contractor, and a copy forwarded to the TPT
- Include the proposed Authorised Inspection Authority (where applicable - for pressurised equipment and systems)
- Include a schedule of proposed quality records

The PQP shall be controlled and re-submitted for approval when required to incorporate any change necessary during the Contract duration to ensure that the document is maintained as an effective control, change management and records. The change management will be done to an agreed policy or procedure.

Note: Where the Supplier/Contractor is required to provide a PQP, no work shall commence until the PQP is approved by TPT.

5.2 Procedures

The Supplier/Contractor's PQP and procedures shall address the system elements and activities appropriate to the Scope of Work, in compliance with the specified Quality Standard.

Where specified, the Supplier/Contractor shall submit copies of Quality Procedures for review. In addition, the Supplier/Contractor shall ensure that copies of all Procedures relevant to the Scope of Work are available for reference by TPT at each work location.

These will include, as applicable, the following:

5.2.1 Document Control

The Supplier/Contractor's Project Quality Plan shall provide a description of how TPT provided, Supplier/Contractor and Sub-Supplier/Sub-Contractor documents are to be managed. The description shall address as a minimum:

- Management tools and databases
- Receipt, registration and maintenance
- Internal and external distribution to Employer, third parties and Sub-Contractors
- Management of Codes, Standards and Specifications

-
- Internal review and approval routines and authorities
 - How it is ensured that the correct revisions of documents are available at the point of use including retention periods for all documentation.

5.2.2 Design Control

Where the Supplier/Contractor is responsible for any aspect of design related to their Scope of Work, the Quality Plan shall describe the Supplier/Contractor's methods and procedures for the control of these design activities.

5.2.3 Procurement

Where the Supplier/Contractor is responsible for any aspect of procurement related to their Scope of Work, the Quality Plan shall describe the Supplier/Contractor's methods and procedures for the control of these activities.

5.3 Supplier/Contractor Audits

The Supplier/Contractor shall:

- Carry out audits in accordance with its Quality System at its own and Sub-Supplier/Sub-Contractor's facilities to ensure project quality requirements are being achieved
- Include a QA Audit Schedule in the Supplier/Contractor PQP submitted to TPT prior to commencement of the Scope of Work. The Audit Schedule shall include all audits to be implemented by the Supplier/Contractor and Sub-Supplier/Sub-Contractor during the execution of the Contract
- Where stipulated in the Contract, perform an audit within three months after the Contract start date and thereafter at a minimum frequency of three months. Audit reports shall be submitted to TPT at the completion of each Audit. Where unsatisfactory performance is evident, additional audits shall be performed by the Supplier/Contractor as directed by TPT.

5.4 Transnet Port Terminals Audit

TPT reserves the right to perform quality audits or participate as an observer in Supplier/Contractor audits to verify compliance with the Contractual requirements. The Supplier/Contractor shall within a time frame as agreed upon, correct any adverse audit finding advised by TPT.

6. Inspection and Testing

6.1 General

TPT may, at its discretion perform surveillance inspection at the Supplier/Contractor's premises, SubSupplier/Sub-Contractor's premises or at the location of the Scope of Work.

Dependent on the nature of the Scope of Work and the frequency of inspections TPT may elect to have inspection personnel resident at the place of manufacture, fabrication, or assembly.

The Supplier/Contractor shall ensure free entry and access is given to TPT, certifying authorities and statutory authorities to inspect the Scope of Work and review procedures and quality records at all parts of the Supplier/Contractor's and Sub-Supplier/Sub-Contractor's premises, or at the location of the Scope of Work while any work or test is in progress.

The Supplier/Contractor shall provide TPT with all necessary tools, calibrated measuring equipment, safety equipment and workspace to verify or witness tests in progress.

While TPT is at the Supplier/Contractor's premises, the Supplier/Contractor shall provide, free of charge, reasonable facilities including office facilities and reasonable access to a telephone, facsimile machine and computer connection point.

The Supplier/Contractor shall provide notice in writing in within a time frame time as agreed upon, to allow the attendance of TPT and other representatives at nominated witness and hold points.

6.2 Quality Control Plans

The Supplier/Contractor shall prepare and submit QCP's to TPT for review in accordance with the requirements of the Contract and PQP.

QCP's shall identify all inspection, test and verification requirements to meet the Contractual obligations, specifications, drawings and related details including destructive and non-destructive testing, witness and hold points.

The Supplier/Contractor shall not commence fabrication or manufacture prior to review and approval of the applicable QCP by the TPT.

QCP's shall include reference to all tests specified in the Contract Document.

A typical format for an QCP is shown in Appendix A. The Supplier/Contractor may use its own format providing all information shown in Appendix A is included.

6.3 Inspection Points

The QCP shall identify points in the fabrication, manufacturing and/or installation process that are selected for inspection and shall be denoted by the following inspection codes:

- Hold Point (H) Inspection point in the manufacturing cycle, beyond which work shall not proceed without the specified activity, work or function being witnessed. Holding points require written notification to TPT.
- Witness Point (W) An inspection point in the manufacturing cycle that will be witnessed or verified. If TPT confirms it is unable to attend after being provided with the written notification then manufacture may proceed. Witness points require written notification to TPT.
- Review Point (R) A point at which products and quality records are verified and endorsed. Review points are not notifiable points.
- Surveillance (S) An inspection point in the manufacturing cycle during which any activity, work or function is observed. No formal notification is required.

The Supplier/Contractor shall maintain the status of testing and inspection by progressively having the QCP's signed off.

6.4 Revision to Quality Control Plans

Revision of the QCP shall be subject to the same submission, review and acceptance routines as described for the original QCP issue

6.5 Kick Off Meeting

After the Contract start date, and prior to manufacture, TPT will require a Kick Off Meeting with the Supplier/Contractor to discuss fully the implications of meeting TPT quality requirements. This meeting may be held as part of the Contract kick-off meeting for each package or may be a separate meeting, subject to the critical or complex nature of the work. This requirement for a pre-inspection meeting may be repeated when sub-Supplier/Contractors of key equipment are engaged.

After mobilization of the Contractor, and prior to the commencement of any construction activities, TPT will arrange for a Quality kick-off meeting to discuss fully the implications of meeting the projects' quality requirements. This meeting may be held as part of the formal kick-off meeting for each contractor, or may be a separate meeting subject to the critical or complex nature of the work.

6.6 Schedule of Inspection

The Supplier/Contractor shall submit a Schedule showing the proposed dates for inspections and tests nominated in the QCP where witness and hold points are required. The Schedule shall be regularly updated with progress and issued to TPT to show the current inspection and test status.

6.7 Field Inspection Checklists

For site installation and construction activities, the Supplier/Contractor shall prepare Field Inspection Checklists (FIC's) to permit inspection and testing of installed equipment and constructed facilities in accordance with the respective QCP's.

FIC's shall be provided to TPT for initial review, and shall be used to record the results of inspection and testing (where applicable), and on completion be submitted to TPT to confirm satisfactory completion of the tests and inspections at nominated QCP witness and hold points.

6.8 Inspection Notification

The Supplier/Contractor shall notify TPT in writing at least two calendar weeks prior to the advent of inspections or tests that require witnessing.

For inspections or tests within the country, arrangements shall be confirmed at least two working days before the event. For inspection and tests outside of the country, arrangements shall be confirmed at least seven working days before the event.

Inspection notifications shall include the following essential information:

- Contract Number
- Location of Inspection or Test
- Nature of Inspection or Test
- Date and Time of Inspection or Test
- Name and telephone number of the Supplier/Contractor's Representative.

6.9 Inspection and Testing

The Supplier/Contractor is responsible for the conduct of all Supplier/Contractor inspections and tests, and includes:

- Documenting inspection and tests result in the QCP's and relevant FIC's
- Progressively inspecting the quality of the Scope of Work performed, including that of all Sub-Supplier/Sub-Contractors
- Inspecting to meet all Contractual requirements, in number, type and form
- Inspecting day to day activities, material receipts, issue of material for installation, in-process inspections, and final inspections.

Completed original QCP's and FIC's shall be submitted to TPT in the DP

6.10 Inspection Release

At completion of the Scope of Work, either in total or in phases, TPT may issue an Inspection Release Report (IRR) or a waiver of inspection.

The issue of either an inspection release or waiver of inspection does not relieve the Supplier/Contractor of its obligations under the Contract. The Supplier/Contractor shall ensure a copy of the release note and final expediting release note for transport, where appropriate, is attached to the delivery docket and accompanies the Work to the designated destination indicated in the Contract. Items delivered to TPT without a copy of these documents may not be accepted.

A copy of the inspection release or waiver of inspection shall be included in the DP.

6.11 Special Processes

It is the Supplier/Contractor's responsibility to ensure that all processes which require prequalified procedures and/or work methods are tested and qualified before work begins. This typically covers such activities as welding, non-destructive testing, special fabrication techniques and painting. Unless specified such procedures are the Supplier/Contractor's responsibility and do not require submission to TPT before work begins. When such procedures are requested, no work shall commence until procedures are approved by TPT.

It is the Supplier/Contractor's responsibility to ensure all operators are qualified for the processes in accordance with the procedure and/or applicable standards. Records of qualification of operators shall be maintained by the Supplier/Contractor and made available to TPT when requested.

Records of qualification of procedures and processes shall be maintained by the Supplier/Contractor in accordance with the applicable procedure or code.

6.12 Welding Procedures

Where the Supplier/Contractor's Scope of Work includes fabricated weldments, Welding Procedure Specifications (WPS) defining the method, preparation and sequences to be adopted to achieve a satisfactory welded joint shall be provided for all weld types required in the execution of the Supplier/Contractor's Scope of Work. The procedure shall only be submitted to TPT when requested in the Contract.

WPS shall include all welding essential and non-essential variables for each process used, including appropriate test results and shall comply with the standard or code pertaining to welding required in the execution of the Supplier/Contractor's Scope of Work.

When requested in the Contract a suitably marked "weld map" shall be completed by the Supplier/Contractor for all items to be fabricated. A summary of WPS shall be prepared and when used, shall be identified on the weld map.

Where TPT approval is required, fabrication shall not commence until written approval of WPS and Welding Procedure Qualification Records (WPQR) is received by the Supplier/Contractor. No welding fabrication will be accepted that is not covered by an TPT approved WPS/WPQR.

Welding Procedure Qualification (WPQ) tests may be witnessed by TPT and/or an independent inspection authority. Testing of the specimens prepared during the WPQ Tests shall be carried out by an independent approved testing laboratory independent of the Supplier/Contractor. In certain instances, a certificate to EN 10204 3.1 B may be required which will be clarified at Tender review and clarification stage.

Where actual weld deposit analysis and weld metal physical properties are required for procedure qualification, the information shall be taken from the procedure qualification tests. Data listed in the catalogues of the manufacturer of welding consumables is not acceptable.

Welders/welding operators shall be qualified in accordance with the relevant welding code prior to commencing production fabrication. Specific Welder Qualifications (WQ's) records will be reviewed by TPT in the Supplier/Contractor's works and should NOT be submitted for review.

A register of welders qualified to work shall be maintained by the Supplier/Contractor.

6.13 Material Traceability

Where, and to the extent that material traceability is required, the Contractor shall provide its procedures for the maintenance of material identification throughout all phases of manufacture. Methods of identification, routines for re-stamping or stencilling as appropriate shall be defined and agreed with the Employer.

Adequate records shall be maintained throughout construction enabling traceability of key materials from final product back to original material certificates. The material traceability records shall form part of the DP

The Contractor shall prepare a schedule of materials and equipment that are subject to traceability requirements.

6.14 Material Certification

Where specified in the Contract the following certificates shall be provided to TPT and included in the DP.

- Type A: A Supplier/Contractor's certificate of compliance with the Contract. This certifies that the goods or services are supplied in compliance with the Contract without mention of any test results (EN10204 certificate 2.1).
- Type B: A certificate issued by a laboratory or test facility independent of the Supplier/Contractor's works. It shall quote test results carried out on the product supplied and state whether compliance with the relevant technical standard, code etc has been complied with. (EN 10204 certificate 3.1 B).
- Type C: The same as Type B, the tests are to be witnessed by a third party (EN 10204 certificate 3.1C).

7. Non Conforming Products

7.1 General

The Supplier/Contractor shall establish and maintain procedures to control material or products that do not meet the specified requirements.

All Supplier/Contractor product and/or materials identified as not conforming to requirements shall be dealt with promptly as follows:

- If the Supplier/Contractor discovers material or product which is not in accordance with the requirements of the Contract, i.e. a non conformance (NCR), the Supplier/Contractor shall promptly initiate the non-conformance procedure in terms of the Supplier/Contractor's Quality Management System, advise TPT promptly, and provide a copy of the NCR to TPT
- If TPT or it's agent identifies a non conformance an TPT NCR may be raised.
- Originals of all closed out NCR's shall be included in the DP.

7.2 Corrective and Preventative Action

If the Supplier/Contractor proposes a disposition of any non conforming materials or product which varies from the requirements of the Specification or Contract, such a proposal shall be submitted in writing to TPT whose decision on the proposal shall be obtained in writing before the non conforming material or product is covered up or incorporated into the Works, or is the subject of any other disposition.

The disposition of non-conformances which do not vary the requirements of the Contract, specification or drawings may be approved by the Supplier/Contractor following discussion and agreement with TPT.

8. Concession Requests and Technical Queries

8.1 Concession Requests

Where a Supplier/Contractor requests a Concession to deviate from the requirements of the Contract or specified requirements, the Supplier/Contractor shall raise the request with TPT using the format as shown in Annexure B.

The Concession Requests shall clearly identify all elements of the proposed deviation together with any resulting technical, commercial and/or schedule impacts.

Completed original Concession Requests shall be included in the DP.

8.2 Technical Queries

For clarification of technical issues (only), Supplier/Contractor may submit a Technical Query Note (TQN) to TPT in accordance with the Contract.

The TQN shall clearly identify all elements of the query, and all supporting documentation and/or drawings shall be attached where appropriate.

Completed original TQN's shall be included in the DP.

9. Inspection, Measuring and Test Equipment

9.1 Calibration

The Supplier/Contractor, including its Sub-Supplier/Sub-Contractors shall ensure the calibration of test and measuring equipment is performed and maintained in accordance with the relevant Supplier/Contractor procedures and/or the equipment manufacturer's specifications.

Where calibration is required by an external laboratory, the Supplier/Contractor shall ensure that the facility selected for calibration possesses current certification. Calibration certificates shall contain a statement that the test equipment is accurate to within specified tolerances.

The Supplier/Contractor should establish the frequency of calibration for each item of equipment (including jigs, fixtures or templates) and record the details in a 'Measuring and Test Equipment Register' (or similar).

9.2 Use of Inspection, Measuring and Test Equipment

The Supplier/Contractor shall ensure that authorised equipment users:

- Use the equipment in accordance with manufacturers instructions, and accepted industry practices
- Ensure the equipment is covered by a current calibration certificate
- Conduct the measurements or tests in accordance with the equipment manufacturer's specifications or other relevant specification
- Prior to commencement of each inspection or test activities:
 - Identify the measurements to be made
 - Determine the accuracy required
 - Select the appropriate inspection, measuring or test equipment for the scope of work.

9.3 Verification of Previous Test Results

Where the calibration status of the equipment is unknown, expired or has doubtful accuracy, the equipment shall immediately be quarantined, and tagged according to Supplier/Contractor's Quality System procedures. The Supplier/Contractor shall then arrange for either in-house or external calibration, and:

- review all previous test results associated with the suspect equipment
- identify the inspections, measurements or tests required to re-validate the results
- ensure that suitable re-testing is performed with calibrated equipment
- document the results of the re-testing on the respective inspection and test documentation.

10. Quality Records

Supplier/Contractors shall maintain Quality Records necessary to provide objective evidence that demonstrates and verifies achievement of the QA / QC requirements associated with the Scope of Work. All Quality Records, including original source material test certificates and non destructive test reports, shall be retained by the Supplier/Contractor during the project, and be provided to TPT at the times, and in the quantities specified in the Contract.

The Supplier/Contractor shall collate all quality records in the DP and submit the DP to TPT in accordance with the Contract and all referenced standards and specifications. This DP shall be compiled progressively, and shall be available for review at all phases of manufacture or construction activities.

The Scope of Work shall not be complete until the Supplier/Contractor's DP including the quality records from Sub-Supplier/Sub-Contractors have been reviewed and accepted by TPT.

The DP shall be compiled progressively during the execution of the Scope of Work and shall be made available for review by TPT as required.



Annexure B - Request for Concession

Request for Concession		No: _____ of 2	
A.SUPPLIER/CONTRACTOR SUPPLIED INFORMATION			
SUPPLIER/CONTRACTOR NAME:		CONTRACT NO.:	
SUPPLIER/CONTRACTOR CONCESSION NO.:		DATE:	
Required concession applicable to: (Item/Material/Equipment/Area)			
Description of Concession — Revised Requirements:			
Justification:			
(NOTE: This concession will be rejected if the following information is not provided):			
(i) VALUE OF BENEFIT TO CLIENT	(ii) AGREE TO AN EXTENSION OF THE WARRANTY	YES	NO
S/R	IF "YES" WHAT PERIOD?		
References:			
Original Requirements	reference:		
Rev.:	Specification	N	Rev.:
Drawing No.:	Rev.:	o.	Rev.:
Drawing No.:	Rev.:	:	Rev.:
Attached applicable	documentation:	N	
Requested by:			
(Supplier/Contractor) Name:	Signature		D
Note: Sections B to F on Page 2			

Request for Concession No:			
B. SITE ADMINISTERED CONTRACT?	<input type="checkbox"/> Yes	<input type="checkbox"/> Nn	<input type="checkbox"/> Go to "D"
Possible QC implications:			
<input type="checkbox"/> Recommendations <input type="checkbox"/> Recommended		<input type="checkbox"/> Rejected	
Site Construction Manager:		Signature:	Date:
Site Engineer:		Signature:	Date:
C. RECOMMENDATION BY CONTRACT ADMINISTRATOR: Name:			
Signature		Date:	
D. RECOMMENDATION BY ENGINEERING:			
<input type="checkbox"/> Recommended		<input type="checkbox"/> Rejected	
<input type="checkbox"/> Conditional, with the following		<input type="checkbox"/> Conditional, with the following	
recommendations:			
Package Engineer:		Signature:	Date:
Lead Discipline Engineer:		Signature:	Date:
Engineering Manager:		Signature:	Date:
Comments:			
E. PROJECT MANAGER DISPOSITION:			
Accepted <input type="checkbox"/>		Rejected <input type="checkbox"/>	
Name:		Signature	Date:
F. EMPLOYER DISPOSITION:			
Accepted <input type="checkbox"/>		Rejected <input type="checkbox"/>	